

PRICE BID (SCHEDULE-B)

NAME OF WORK:- Supply,Installation,Testing and Commissioning of Inverter Ductable Air Conditioning Work at Lezim Hall in Yashada.

Sr. No	Item Description	Qty	Unit	Rate per Unit (Rs.)	Amount (Rs.)
A	For indoor Unit				
1	Supply of ductable split unit of 8.5 TR (upto 5 % on higher side) suitable for 230/250 v, 50 cycles, AC supply with environment friendly refrigerant with provided copper piping and drainage.	3	No		
2	Erecting, installation, testing and commissioning of 8.5 TR (upto 5 % on higher side) Inverter ductable spilt AC unit (3 IDU & 3 ODU)	6	No		
3	Supplying & erecting hard drawn copper pipe suitable for air conditioning system having 22 SWG thickness and inner dia/size 12 mm complete. Supplying & erecting hard drawn copper pipe suitable for air conditioning system having 22 SWG thickness and inner dia / size 12mm complete.	40	RM		
4	Supplying & erecting hard drawn copper pipe suitable for air conditioning system having 22 SWG thickness and inner dia / size 16 mm complete.	40	RM		
5	S,I, T & C of ducting for supply air of AC units with 20/22 SWG	180	Sqm		
6	Supplying & erecting tile type modular diffuser made from aluminum sheet complete with powder coated matching to the ceiling shade for provided supply & return air.	30	No		
7	Providing and fixing of control cable for 8.5 tr DSAC units	180	Sqm		
8	Providing and fixing of Acoustic insulation.	40	Sqm		
9	Providing and fixing of Nitril Rubber 13mm Thermal insulation.	180	Sqm		
10	Providing and fixing of GI Duct Dampers	6	Sqm		
11	Providing and fixing of Aluminum Chollar Dampers	6	Sqm		
12	Providing and fixing of Aluminum Continuous Grill	17	Sqm		
13	Providing and fixing of Fresh Air Arrangement	3	Lot		
14	Providing and fixing of Canvass Connection to DSAC	3	No		
15	Providing and fixing of MS fabrication angle 50x5mm Size	6	No		

PRICE BID (SCHEDULE-B)... cont. from previous page

NAME OF WORK:- Supply,Installation,Testing and Commissioning of Inverter Ductable Air Conditioning Work at Lezim Hall in Yashada.

Sr. No	Item Description	Qty	Unit	Rate per Unit (Rs.)	Amount (Rs.)
B	For Outdoor Unit				
16	Installation & charging and commissioning	3	No		
17	Supply & Installation of PVC drain piping with 6mm thk nitrile rubber insulation	30	Mtr		
18	Supplying, erecting & terminating XLPE armoured cable 4 core 4 sq. mm. copper conductor continuous 5.48 sq. mm. (12 SWG) G.I. earth wire complete erected with glands & lugs, on wall/ trusses/ pole or laid in provided trench/ pipe as per specification.	70	Mtr		
19	GST on Item (1) @ 28%				
20	GST on Item (2 to 18) @ 18%				
21	Total Amount including all applicable Taxes (Rs.)				

I agree to execute the above work as per Schedule - B at Cost in Rupees (Including GST, Taxes, Levies and Transport) Figures ----- In Words -----

Signature & Stamp of Agency