

यशवंतराव चव्हाण विकास प्रशासन प्रबोधिनी

(महाराष्ट्र शासनाची अंगीकृत संस्था) Yashwantrao Chavan Academy of Development Administration (A Government of Maharashtra Organisation)



No. EMR/3624/G.L.J.P. Date: - 06/05/2025

To,

Sir,

Kindly forward your quotation for the following supplies / works.

Subject :- Quotation for Supply, Installation, Testing and Commissioning of 1.5 Ton & 2.0 Ton 5 Star Inverter Split AC's for PMB 4th floor and Admin Ground, 3rd floor in YASHADA.

Supply, Installation, Testing and Commissioning of 1.5 Ton & 2.0 Ton 5 Star Inverter Split AC's for PMB 4th floor and Admin Ground, 3rd floor in YASHADA

	Part - A					
Sr · No	Description	Make and Model	ISEER value of product offered	Qty in Nos	Basic Rate per unit (W/O GST)	Amount
1	2	3	4	5	6	7
1	Residential section : Supplying, installing, testing and commissioning 5 Star split type variable speed Inverter technology room Air conditioning unit 2 TR capacity having minimum ISEER value of 5.0, suitable to operate on 250V, 50 cycles, A.C. supply having 1 no of air handling unit hi wall / floor mounting type complete with refrigerant R410 A/R32 and copper condenser and evaporators at position.	Bluestar / Daikin /Voltas		1		
2	Residential section : Supplying, installing, testing and commissioning 5 Star split type variable speed Inverter technology room Air conditioning unit 1.5 TR capacity having minimum ISEER value of 5.4, suitable to operate on	Bluestar / Daikin /Voltas		12		

250V, 50 cycles, A.C. supply having 1 no of air handling unit hi wall / floor mounting type complete with refrigerant R410 A/R32 and copper condenser and evaporators at position.				
GST @_28_% Total quoted amount with GST for Part - A				

Part - B					
Sr No	Description	Qty	Unit	Rate per unit	Total Amount (Col. 3 X 5)
1	2	3	4	5	6
1	Supply and Installation of powder coated bracket stand (wall mounted / floor mounted) suitable for 1.5 / 2.0 TR split ac in appropriate manner with all required accessories complete as directed by Engineer in charge.	13	Nos		
2	Supply and Installation of copper piping (for suction and discharge) of appropriate size in appropriate manner suitable for machines provided with all required accessories complete as directed by Engineer in charge.	75	mtr		
3	Supply and Installation of 1.5 sqmm. 4 core copper flexible wire in appropriate manner suitable for machines provided with all required accessories complete as directed by Engineer in charge.	75	mtr		
4	Supply and Installation hard PVC drain pipe of appropriate size in appropriate manner suitable for machines provided with all required accessories complete as directed by Engineer in charge.	55	mtr		
5	Providing and driling core cuts in beams and columns complete with finishing to wall as directed by Engineer in charge as per site conditions	50	Inches		
				al of Part - B	
L	GST @_18%				
	Total quoted amount with GST for Part - B				

Column 7 of part - A	
Column 6 Part - B	

Total cost for evaluation : (part - $A +$	
Part - B) :	

I agree to executive the above work at a total cost of (Column 7 of Part - A + Column 6 Part - B) Rs -_____/- (with GST)

(In words Rs _____

GST)

- If calculations of above are calculated wrongly, it will be recalculated at the time of finalisation of tender/quotation during evaluation of tender.
- 50% machines shall be provided for further 1 year with the same rete if YASHADA needed.

<u>Note: -</u>

- The sealed covers containing quotations with superscription like "Quotation for Supply, Installation, Testing and Commissioning of 1.5 Ton & 2.0 Ton 5 Star Inverter Split AC's for PMB 4th floor and Admin Ground, 3rd floor in YASHADA." Should be addressed to the undersigned (Estate Department, Yashada) and sent to reach from 06/05/2025 to on or Before 14/05/2025 at 3.00 pm.
- 2. Quotations after the said date will not be entertained. Undersigned reserves the right to reject all quotations without assigning reasons, therefore.
- 3. The vendor should come and examine the site at Yashada and contact to Estate Department, YASHADA before quoting the rates, if needed.
- 4. The Lowest quote (L1) shall be finalized based on Quoted Total Amount including GST
- 5. 5% of Security Deposit vide DD shall be deposited to Estate Department before accepting work order within 5 days after intimating by any mean. Security deposit shall be refunded after 1 year of warranty period.
- 6. Directives of Competent person or Engineer In charge shall be followed during whole work.
- 7. Agency shall provide Pan Card copy.
- 8. Agency shall provide GST registration certificate copy.
- 9. Agency shall provide Shop Act or Any Govt. Competent Authority Registered certificate and Certificate of registration as AC manufacturers /Authorized Dealers or Distributors or Bidders for Air Conditioning units / PWD registered contractor, as applicable.
- 10. Quotation shall be provided on Letter head.
- 11. Scope of Work : Includes Supply Installation Testing and Commissioning of Supply, Installation, Testing and Commissioning of 1.5 Ton & 2.0 Ton 5 Star Inverter Split AC's for PMB 4th floor and Admin Ground, 3rd floor in YASHADA as per standard PWD specification and directed by Engineer in-charge.
- 12. As per OEM's standard norms Preventive visits shall be done and breakdown services shall be provided as and when required during 1 year of warranty period.
- 13. Warranty shall be applicable as described in Item Description.

(Registrar) Yashwantrao Chavan Academy of Development Administration, Pune - 411 007

(with

Quotation on Company Letter head